

LAMPIRAN 1

(Bar Chart Pekerjaan Struktur Hotel Grand Seriti)



RICKY MARTUA SIHOMBING

NRP: 0521053

NO.	ITEM PEKERJAAN	VOLUME	SAT.	BOBOT	TAHUN 2007											KETERANGAN
					21-Jul P-1	28-Jul P-2	04-Agust P-3	11-Agust P-4	18-Agust P-5	25-Agust P-6	01-Sep P-7	08-Sep P-8	15-Sep P-9	22-Sep P-10	29-Sep P-11	
	PEKERJAAN STRUKTUR															
A	LANTAI 1 (SATU)															
1	Balok B-1 (200x400)															
	- Besi Beton	464,76	kg	0,0512												
	- Bekisting	21,28	m²	0,0243												
	- Beton K-300	1,49	m³	0,0133												
2	Balok B-2 (200x400)															
	- Besi Beton	218,34	kg	0,0241												
	- Bekisting	8,80	m²	0,0101												
	- Beton K-300	0,62	m³	0,0055												
3	Balok B-3 (200x400)															
	- Besi Beton	2.047,84	kg	0,2258												
	- Bekisting	59,81	m²	0,0684												
	- Beton K-300	4,41	m³	0,0392												
4	Balok B-4 (200x400)															
	- Besi Beton	160,41	kg	0,0177												
	- Bekisting	5,20	m²	0,0059												
	- Beton K-300	0,36	m³	0,0032												
5	Balok B-5 (200x600)															
	- Besi Beton	370,27	kg	0,0408												
	- Bekisting	19,80	m²	0,0227												
	- Beton K-300	1,58	m³	0,0141												
6	Balok B-6 (200x600)															
	- Besi Beton	442,42	kg	0,0488												
	- Bekisting	23,66	m²	0,0271												
	- Beton K-300	1,89	m³	0,0168												
7	Balok B-7 (200x600)															
	- Besi Beton	1.710,68	kg	0,1886												
	- Bekisting	83,64	m²	0,0957												
	- Beton K-300	6,69	m³	0,0595												
8	Balok B-8 (200x600)															
	- Besi Beton	2.020,03	kg	0,2228												
	- Bekisting	83,90	m²	0,0960												
	- Beton K-300	6,71	m³	0,0597												
9	Balok B-9 (200x600)															
	- Besi Beton	161,22	kg	0,0178												
	- Bekisting	7,09	m²	0,0081												
	- Beton K-300	0,57	m³	0,0050												
10	Balok B-10 (250x600)															
	- Besi Beton	613,36	kg	0,0676												
	- Bekisting	30,06	m²	0,0344												
	- Beton K-300	2,89	m³	0,0257												

TIME SCHEDULE
PROYEK GRAND SERITI HOTEL
PEKERJAAN STRUKTUR
JL. HEGARMANAH NO.9, BANDUNG

NO.	ITEM PEKERJAAN	VOLUME	SAT.	BOBOT	TAHUN 2007											KETERANGAN
					21-Jul P-1	28-Jul P-2	04-Agust P-3	11-Agust P-4	18-Agust P-5	25-Agust P-6	01-Sep P-7	08-Sep P-8	15-Sep P-9	22-Sep P-10	29-Sep P-11	
	- Besi Beton	523,00	kg	0,0577												
	- Bekisting	31,62	m ²	0,0362												
	- Beton K-300	3,04	m ³	0,0270												
13	Balok B-13 (250x600)															
	- Besi Beton	122,84	kg	0,0135												
	- Bekisting	5,50	m ²	0,0063												
	- Beton K-300	0,53	m ³	0,0047												
14	Balok B-14 (250x600)															
	- Besi Beton	523,47	kg	0,0577												
	- Bekisting	23,44	m ²	0,0268												
	- Beton K-300	2,25	m ³	0,0200												
15	Balok B-15 (250x600)															
	- Besi Beton	85,95	kg	0,0095												
	- Bekisting	4,21	m ²	0,0048												
	- Beton K-300	0,40	m ³	0,0036												
16	Balok B-17 (400x600)															
	- Besi Beton	89,06	kg	0,0098												
	- Bekisting	3,36	m ²	0,0038												
	- Beton K-300	0,46	m ³	0,0041												
17	Balok B-18 (300x600)															
	- Besi Beton	609,62	kg	0,0672												
	- Bekisting	19,50	m ²	0,0223												
	- Beton K-300	2,16	m ³	0,0192												
18	Balok B-19 (300x600)															
	- Besi Beton	817,03	kg	0,0901												
	- Bekisting	29,66	m ²	0,0339												
	- Beton K-300	3,29	m ³	0,0292												
19	Balok B-20 (300x600)															
	- Besi Beton	98,52	kg	0,0109												
	- Bekisting	3,84	m ²	0,0044												
	- Beton K-300	0,42	m ³	0,0038												
20	Balok B-21 (300x600)															
	- Besi Beton	833,15	kg	0,0919												
	- Bekisting	26,65	m ²	0,0305												
	- Beton K-300	2,95	m ³	0,0263												
21	Balok B-22 (300x600)															
	- Besi Beton	322,30	kg	0,0355												
	- Bekisting	11,70	m ²	0,0134												
	- Beton K-300	1,30	m ³	0,0115												
22	Balok B-23 (300x600)															
	- Besi Beton	272,17	kg	0,0300												
	- Bekisting	9,88	m ²	0,0113												
	- Beton K-300	1,09	m ³	0,0097												
23	Balok B-24 (300x600)															
	- Besi Beton	519,88	kg	0,0573												
	- Bekisting	17,68	m ²	0,0202												
	- Beton K-300	1,96	m ³	0,0174												

TIME SCHEDULE
PROYEK GRAND SERITI HOTEL
PEKERJAAN STRUKTUR
JL. HEGARMAH NO.9, BANDUNG

NO.	ITEM PEKERJAAN	VOLUME	SAT.	BOBOT	TAHUN 2007											KETERANGAN
					21-Jul P-1	28-Jul P-2	04-Agust P-3	11-Agust P-4	18-Agust P-5	25-Agust P-6	01-Sep P-7	08-Sep P-8	15-Sep P-9	22-Sep P-10	29-Sep P-11	
24	Balok B-25 (300x600)															
	- Besi Beton	2,947,88	kg	0,3251												
	- Bekisting	88,92	m ²	0,1017												
	- Beton K-300	9,85	m ³	0,0876												
25	Balok B-26 (300x600)															
	- Besi Beton	93,11	kg	0,0103												
	- Bekisting	3,38	m ²	0,0039												
	- Beton K-300	0,37	m ³	0,0033												
26	Balok B-27 (300x600)															
	- Besi Beton	736,64	kg	0,0812												
	- Bekisting	21,06	m ²	0,0241												
	- Beton K-300	2,33	m ³	0,0208												
27	Balok B-28 (300x600)															
	- Besi Beton	198,75	kg	0,0219												
	- Bekisting	9,88	m ²	0,0113												
	- Beton K-300	1,09	m ³	0,0097												
28	Balok B-29 (300x600)															
	- Besi Beton	706,23	kg	0,0779												
	- Bekisting	20,28	m ²	0,0232												
	- Beton K-300	2,25	m ³	0,0200												
29	Balok B-30 (300x600)															
	- Besi Beton	458,72	kg	0,0506												
	- Bekisting	15,60	m ²	0,0178												
	- Beton K-300	1,73	m ³	0,0154												
30	Balok B-31 (300x800)															
	- Besi Beton	218,44	kg	0,0241												
	- Bekisting	12,92	m ²	0,0148												
	- Beton K-300	1,55	m ³	0,0138												
31	Balok B-32 (300x800)															
	- Besi Beton	236,80	kg	0,0261												
	- Bekisting	12,92	m ²	0,0148												
	- Beton K-300	1,55	m ³	0,0138												
32	Balok B-33 (300x800)															
	- Besi Beton	613,90	kg	0,0677												
	- Bekisting	24,14	m ²	0,0276												
	- Beton K-300	2,90	m ³	0,0258												
33	Balok B-34 (300x800)															
	- Besi Beton	666,46	kg	0,0735												
	- Bekisting	24,82	m ²	0,0284												
	- Beton K-300	2,98	m ³	0,0265												
34	Balok B-35 (300x800)															
	- Besi Beton	153,61	kg	0,0169												
	- Bekisting	6,80	m ²	0,0078												
	- Beton K-300	0,82	m ³	0,0073												
35	Balok B-36 (300x900)															
	- Besi Beton	393,48	kg	0,0434												
	- Bekisting	14,44	m ²	0,0165												

TIME SCHEDULE
PROYEK GRAND SERITI HOTEL
PEKERJAAN STRUKTUR
JL. HEGARMANAH NO.9, BANDUNG

NO.	ITEM PEKERJAAN	VOLUME	SAT.	BOBOT	TAHUN 2007											KETERANGAN
					21-Jul P-1	28-Jul P-2	04-Agust P-3	11-Agust P-4	18-Agust P-5	25-Agust P-6	01-Sep P-7	08-Sep P-8	15-Sep P-9	22-Sep P-10	29-Sep P-11	
	- Beton K-300	1,78	m ³	0,0158												
36	Balok B-37 (300x900)															
	- Besi Beton	899,47	kg	0,0992												
	- Bekisting	38,38	m ²	0,0439												
	- Beton K-300	4,73	m ³	0,0420												
37	Balok B-38 (300x900)															
	- Besi Beton	105,28	kg	0,0116												
	- Bekisting	4,75	m ²	0,0054												
	- Beton K-300	0,59	m ³	0,0052												
38	Balok B-39 (400x700)															
	- Besi Beton	1.004,25	kg	0,1107												
	- Bekisting	17,60	m ²	0,0201												
	- Beton K-300	2,55	m ³	0,0227												
39	Balok B-40 (400x650)															
	- Besi Beton	1.021,52	kg	0,1126												
	- Bekisting	27,00	m ²	0,0309												
	- Beton K-300	3,82	m ³	0,0339												
40	Balok B-41 (400x650)															
	- Besi Beton	510,76	kg	0,0563												
	- Bekisting	13,50	m ²	0,0154												
	- Beton K-300	1,91	m ³	0,0170												
41	Balok B-42 (400x650)															
	- Besi Beton	445,55	kg	0,0491												
	- Bekisting	13,50	m ²	0,0154												
	- Beton K-300	1,91	m ³	0,0170												
42	Balok B-43 (150x300)															
	- Besi Beton	117,73	kg	0,0130												
	- Bekisting	4,18	m ²	0,0048												
	- Beton K-300	0,21	m ³	0,0018												
43	Balok B-44 (300x900)															
	- Besi Beton	76,71	kg	0,0085												
	- Bekisting	4,18	m ²	0,0048												
	- Beton K-300	0,51	m ³	0,0046												
44	Balok B-45 (400x650)															
	- Besi Beton	860,67	kg	0,0949												
	- Bekisting	16,20	m ²	0,0185												
	- Beton K-300	2,29	m ³	0,0204												
45	Balok B-46 (300x600)															
	- Besi Beton	382,29	kg	0,0422												
	- Bekisting	9,88	m ²	0,0113												
	- Beton K-300	1,09	m ³	0,0097												
46	Plat (t=12cm)															
	- Wiremesh M7 (Double Layer)	286,11	m ²	0,3788												
	- Besi Beton	70,96	kg	0,0078												
	- Bekisting	286,11	m ²	0,3273												
	- Beton K-300	34,33	m ³	0,3054												
47	Plat (t=15cm)															

TIME SCHEDULE
PROYEK GRAND SERITI HOTEL
PEKERJAAN STRUKTUR
JL. HEGARMAH NO.9, BANDUNG

NO.	ITEM PEKERJAAN	VOLUME	SAT.	BOBOT	TAHUN 2007											KETERANGAN
					21-Jul P-1	28-Jul P-2	04-Agust P-3	11-Agust P-4	18-Agust P-5	25-Agust P-6	01-Sep P-7	08-Sep P-8	15-Sep P-9	22-Sep P-10	29-Sep P-11	
	- Wiremesh M8 (Double Layer)	921,96	m ²	1,8461												
	- Besi Beton	228,65	kg	0,0252												
	- Bekisting	921,96	m ²	1,0548												
	- Beton K-300	138,29	m ³	1,2302												
48	Kolom K-1 (500x800)															
	- Besi Beton	4.974,13	kg	0,5485												
	- Bekisting	197,63	m ²	0,2486												
	- Beton K-300	30,40	m ³	0,2705												
49	Kolom K-2 (500x800)															
	- Besi Beton	2.260,97	kg	0,2493												
	- Bekisting	89,83	m ²	0,1130												
	- Beton K-300	13,82	m ³	0,1229												
50	Kolom K-3 (500x800)															
	- Besi Beton	485,13	kg	0,0535												
	- Bekisting	17,97	m ²	0,0226												
	- Beton K-300	2,76	m ³	0,0246												
51	Kolom K-4 (600x600)															
	- Besi Beton	1.570,87	kg	0,1732												
	- Bekisting	49,75	m ²	0,0626												
	- Beton K-300	7,46	m ³	0,0664												
52	Kolom K-5 (250x600)															
	- Besi Beton	1.072,88	kg	0,1183												
	- Bekisting	35,24	m ²	0,0443												
	- Beton K-300	3,11	m ³	0,0277												
53	Kolom K-6 (500x800)															
	- Besi Beton	452,19	kg	0,0499												
	- Bekisting	17,97	m ²	0,0226												
	- Beton K-300	2,76	m ³	0,0246												
54	Kolom K-7 (500x800)															
	- Besi Beton	1.102,03	kg	0,1215												
	- Bekisting	35,93	m ²	0,0452												
	- Beton K-300	5,53	m ³	0,0492												
55	Kolom K-8 (500x800)															
	- Besi Beton	1.167,91	kg	0,1288												
	- Bekisting	35,93	m ²	0,0452												
	- Beton K-300	5,53	m ³	0,0492												
56	Kolom K-9 (500x800)															
	- Besi Beton	1.940,54	kg	0,2140												
	- Bekisting	71,86	m ²	0,0904												
	- Beton K-300	11,06	m ³	0,0983												
57	Tangga Front Office ke Elevasi +3,27															
	- Besi Beton	117,48	kg	0,0130												
	- Bekisting	3,71	m ²	0,0042												
	- Beton K-300	0,50	m ³	0,0045												
58	Tangga Depan ke Elevasi +3,27															
	- Besi Beton	271,10	kg	0,0299												
	- Bekisting	8,55	m ²	0,0098												

TIME SCHEDULE
PROYEK GRAND SERITI HOTEL
PEKERJAAN STRUKTUR
JL. HEGARMANAH NO.9, BANDUNG

NO.	ITEM PEKERJAAN	VOLUME	SAT.	BOBOT	TAHUN 2007											KETERANGAN
					21-Jul P-1	28-Jul P-2	04-Agust P-3	11-Agust P-4	18-Agust P-5	25-Agust P-6	01-Sep P-7	08-Sep P-8	15-Sep P-9	22-Sep P-10	29-Sep P-11	
	- Beton K-300	1,16	m ³	0,0103												
	Sub Total IV.B.															
B	LANTAI 2 (DUA)															
1	Balok B-1 (150x300)															
	- Besi Beton	125,34	kg	0,0139												
	- Bekisting	3,85	m ²	0,0044												
	- Beton K-300	0,19	m ³	0,0017												
2	Balok B-2 (200x400)															
	- Besi Beton	200,38	kg	0,0222												
	- Bekisting	7,20	m ²	0,0083												
	- Beton K-300	0,50	m ³	0,0045												
3	Balok B-3 (200x400)															
	- Besi Beton	44,53	kg	0,0049												
	- Bekisting	1,60	m ²	0,0018												
	- Beton K-300	0,11	m ³	0,0010												
4	Balok B-4 (200x400)															
	- Besi Beton	142,49	kg	0,0158												
	- Bekisting	5,12	m ²	0,0059												
	- Beton K-300	0,36	m ³	0,0032												
5	Balok B-5 (200x400)															
	- Besi Beton	487,59	kg	0,0541												
	- Bekisting	17,52	m ²	0,0202												
	- Beton K-300	1,23	m ³	0,0109												
6	Balok B-6 (200x400)															
	- Besi Beton	2.506,85	kg	0,2779												
	- Bekisting	69,80	m ²	0,0806												
	- Beton K-300	4,89	m ³	0,0436												
7	Balok B-7 (200x400)															
	- Besi Beton	944,29	kg	0,1047												
	- Bekisting	25,60	m ²	0,0296												
	- Beton K-300	1,79	m ³	0,0160												
8	Balok B-8 (200x400)															
	- Besi Beton	119,69	kg	0,0133												
	- Bekisting	3,88	m ²	0,0045												
	- Beton K-300	0,27	m ³	0,0024												
9	Balok B-9 (200x400)															
	- Besi Beton	74,04	kg	0,0082												
	- Bekisting	2,40	m ²	0,0028												
	- Beton K-300	0,17	m ³	0,0015												
10	Balok B-10 (300x400)															
	- Besi Beton	1.282,86	kg	0,1422												
	- Bekisting	32,40	m ²	0,0374												
	- Beton K-300	3,02	m ³	0,0270												
11	Balok B-11 (300x600)															
	- Besi Beton	114,60	kg	0,0127												
	- Bekisting	4,16	m ²	0,0048												
	- Beton K-300	0,46	m ³	0,0041												

TIME SCHEDULE
PROYEK GRAND SERITI HOTEL
PEKERJAAN STRUKTUR
JL. HEGARMANAH NO.9, BANDUNG

NO.	ITEM PEKERJAAN	VOLUME	SAT.	BOBOT	TAHUN 2007											KETERANGAN
					21-Jul P-1	28-Jul P-2	04-Agust P-3	11-Agust P-4	18-Agust P-5	25-Agust P-6	01-Sep P-7	08-Sep P-8	15-Sep P-9	22-Sep P-10	29-Sep P-11	
12	Balok B-12 (300x600)															
	- Besi Beton	478,88	kg	0,0531												
	- Bekisting	14,95	m ²	0,0173												
	- Beton K-300	1,66	m ³	0,0148												
13	Balok B-13 (300x600)															
	- Besi Beton	73,22	kg	0,0081												
	- Bekisting	1,82	m ²	0,0021												
	- Beton K-300	0,20	m ³	0,0018												
14	Balok B-14 (300x600)															
	- Besi Beton	2.178,76	kg	0,2415												
	- Bekisting	87,88	m ²	0,1015												
	- Beton K-300	9,73	m ³	0,0869												
15	Balok B-15 (300x600)															
	- Besi Beton	731,54	kg	0,0811												
	- Bekisting	23,40	m ²	0,0270												
	- Beton K-300	2,59	m ³	0,0231												
16	Balok B-16 (300x600)															
	- Besi Beton	2.281,57	kg	0,2529												
	- Bekisting	46,80	m ²	0,0540												
	- Beton K-300	5,18	m ³	0,0463												
17	Balok B-17 (300x600)															
	- Besi Beton	877,85	kg	0,0973												
	- Bekisting	28,08	m ²	0,0324												
	- Beton K-300	3,11	m ³	0,0278												
18	Balok B-18 (300x600)															
	- Besi Beton	682,07	kg	0,0756												
	- Bekisting	19,50	m ²	0,0225												
	- Beton K-300	2,16	m ³	0,0193												
19	Balok B-19 (300x600)															
	- Besi Beton	1.219,24	kg	0,1352												
	- Bekisting	39,00	m ²	0,0450												
	- Beton K-300	4,32	m ³	0,0386												
20	Balok B-21 (300x600)															
	- Besi Beton	1.250,94	kg	0,1387												
	- Bekisting	29,64	m ²	0,0342												
	- Beton K-300	3,28	m ³	0,0293												
21	Balok B-22 (300x600)															
	- Besi Beton	1.799,28	kg	0,1995												
	- Bekisting	27,56	m ²	0,0318												
	- Beton K-300	3,05	m ³	0,0272												
22	Balok B-23 (300x600)															
	- Besi Beton	1.036,75	kg	0,1149												
	- Bekisting	29,64	m ²	0,0342												
	- Beton K-300	3,28	m ³	0,0293												
23	Balok B-24 (300x600)															
	- Besi Beton	654,46	kg	0,0726												
	- Bekisting	19,76	m ²	0,0228												

TIME SCHEDULE
PROYEK GRAND SERITI HOTEL
PEKERJAAN STRUKTUR
JL. HEGARMANAH NO.9, BANDUNG

NO.	ITEM PEKERJAAN	VOLUME	SAT.	BOBOT	TAHUN 2007											KETERANGAN
					21-Jul P-1	28-Jul P-2	04-Agust P-3	11-Agust P-4	18-Agust P-5	25-Agust P-6	01-Sep P-7	08-Sep P-8	15-Sep P-9	22-Sep P-10	29-Sep P-11	
	- Beton K-300	2,19	m³	0,0195												
24	Balok B-25 (300x600)															
	- Besi Beton	1.088,66	kg	0,1207												
	- Bekisting	39,52	m²	0,0456												
	- Beton K-300	4,38	m³	0,0391												
25	Balok B-26 (300x600)															
	- Besi Beton	422,57	kg	0,0468												
	- Bekisting	15,34	m²	0,0177												
	- Beton K-300	1,70	m³	0,0152												
26	Balok B-27 (400x600)															
	- Besi Beton	137,30	kg	0,0152												
	- Bekisting	5,18	m²	0,0060												
	- Beton K-300	0,71	m³	0,0063												
27	Balok B-28 (400x600)															
	- Besi Beton	1.209,37	kg	0,1341												
	- Bekisting	21,42	m²	0,0247												
	- Beton K-300	2,94	m³	0,0262												
28	Plat (t=12cm)															
	- Wiremesh M7 (Double Layer)	816,75	m²	1,0841												
	- Besi Beton	202,55	kg	0,0225												
	- Bekisting	816,75	m²	0,9429												
	- Beton K-300	98,01	m³	0,8746												
	- Water proofing	816,75	m²	1,1590												
29	Kolom K-1 (400x800)															
	- Besi Beton	2.799,57	kg	0,3104												
	- Bekisting	95,57	m²	0,1212												
	- Beton K-300	12,74	m³	0,1137												
30	Kolom K-2 (400x800)															
	- Besi Beton	1.272,53	kg	0,1411												
	- Bekisting	43,44	m²	0,0551												
	- Beton K-300	5,79	m³	0,0517												
31	Kolom K-3 (400x800)															
	- Besi Beton	224,27	kg	0,0249												
	- Bekisting	8,69	m²	0,0110												
	- Beton K-300	1,16	m³	0,0103												
32	Kolom K-4 (600x600)															
	- Besi Beton	821,70	kg	0,0911												
	- Bekisting	26,06	m²	0,0331												
	- Beton K-300	3,91	m³	0,0349												
33	Kolom K-5 (250x500)															
	- Besi Beton	415,57	kg	0,0461												
	- Bekisting	16,29	m²	0,0207												
	- Beton K-300	1,36	m³	0,0121												
34	Kolom K-6 (400x800)															
	- Besi Beton	224,27	kg	0,0249												
	- Bekisting	8,69	m²	0,0110												
	- Beton K-300	1,16	m³	0,0103												

TIME SCHEDULE
PROYEK GRAND SERITI HOTEL
PEKERJAAN STRUKTUR
JL. HEGARMAHA NO.9, BANDUNG

NO.	ITEM PEKERJAAN	VOLUME	SAT.	BOBOT	TAHUN 2007											KETERANGAN
					21-Jul P-1	28-Jul P-2	04-Agust P-3	11-Agust P-4	18-Agust P-5	25-Agust P-6	01-Sep P-7	08-Sep P-8	15-Sep P-9	22-Sep P-10	29-Sep P-11	
35	Kolom K-7 (400x800)															
	- Besi Beton	552,07	kg	0,0612												
	- Bekisting	17,38	m ²	0,0220												
	- Beton K-300	2,32	m ³	0,0207												
37	Kolom K-8 (400x800)															
	- Besi Beton	586,59	kg	0,0650												
	- Bekisting	17,38	m ²	0,0220												
	- Beton K-300	2,32	m ³	0,0207												
38	Kolom K-9 (400x800)															
	- Besi Beton	1.138,99	kg	0,1263												
	- Bekisting	34,75	m ²	0,0441												
	- Beton K-300	4,63	m ³	0,0413												
39	Tangga Front Office ke LT. 3															
	- Besi Beton	117,48	kg	0,0130												
	- Bekisting	3,71	m ²	0,0043												
	- Beton K-300	0,50	m ³	0,0045												
40	Tangga Depan ke LT. 3															
	- Besi Beton	271,10	kg	0,0301												
	- Bekisting	8,55	m ²	0,0099												
	- Beton K-300	1,16	m ³	0,0103												
	Sub Total IV.C.															
C	LANTAI 3 (TIGA)															
1	Balok B-1 (150x300)															
	- Besi Beton	123,55	kg	0,0138												
	- Bekisting	3,80	m ²	0,0044												
	- Beton K-300	0,19	m ³	0,0017												
2	Balok B-2 (200x400)															
	- Besi Beton	421,91	kg	0,0470												
	- Bekisting	15,16	m ²	0,0177												
	- Beton K-300	1,06	m ³	0,0095												
3	Balok B-3 (200x400)															
	- Besi Beton	249,36	kg	0,0278												
	- Bekisting	8,96	m ²	0,0104												
	- Beton K-300	0,63	m ³	0,0056												
4	Balok B-4 (200x400)															
	- Besi Beton	1.723,91	kg	0,1921												
	- Bekisting	48,00	m ²	0,0559												
	- Beton K-300	3,36	m ³	0,0301												
5	Balok B-5 (200x400)															
	- Besi Beton	111,58	kg	0,0124												
	- Bekisting	5,12	m ²	0,0060												
	- Beton K-300	0,36	m ³	0,0032												
6	Balok B-6 (200x400)															
	- Besi Beton	34,55	kg	0,0039												
	- Bekisting	1,12	m ²	0,0013												
	- Beton K-300	0,08	m ³	0,0007												
7	Balok B-7 (200x400)															

TIME SCHEDULE
PROYEK GRAND SERITI HOTEL
PEKERJAAN STRUKTUR
JL. HEGARMANAH NO.9, BANDUNG

NO.	ITEM PEKERJAAN	VOLUME	SAT.	BOBOT	TAHUN 2007											KETERANGAN
					21-Jul P-1	28-Jul P-2	04-Agust P-3	11-Agust P-4	18-Agust P-5	25-Agust P-6	01-Sep P-7	08-Sep P-8	15-Sep P-9	22-Sep P-10	29-Sep P-11	
	- Besi Beton	53,43	kg	0,0060												
	- Bekisting	1,92	m ²	0,0022												
	- Beton K-300	0,13	m ³	0,0012												
8	Balok B-8 (200x400)															
	- Besi Beton	296,15	kg	0,0330												
	- Bekisting	9,60	m ²	0,0112												
	- Beton K-300	0,67	m ³	0,0060												
9	Balok B-9 (200x400)															
	- Besi Beton	961,84	kg	0,1072												
	- Bekisting	28,40	m ²	0,0331												
	- Beton K-300	1,99	m ³	0,0178												
10	Balok B-10 (300x400)															
	- Besi Beton	570,16	kg	0,0635												
	- Bekisting	14,40	m ²	0,0168												
	- Beton K-300	1,34	m ³	0,0120												
11	Balok B-11 (300x600)															
	- Besi Beton	324,92	kg	0,0362												
	- Bekisting	11,05	m ²	0,0129												
	- Beton K-300	1,22	m ³	0,0110												
12	Balok B-12 (300x600)															
	- Besi Beton	1.427,45	kg	0,1591												
	- Bekisting	46,80	m ²	0,0545												
	- Beton K-300	5,18	m ³	0,0464												
13	Balok B-13 (300x600)															
	- Besi Beton	704,97	kg	0,0786												
	- Bekisting	19,31	m ²	0,0225												
	- Beton K-300	2,14	m ³	0,0191												
14	Balok B-14 (300x600)															
	- Besi Beton	1.956,88	kg	0,2181												
	- Bekisting	69,55	m ²	0,0810												
	- Beton K-300	7,70	m ³	0,0690												
15	Balok B-15 (300x600)															
	- Besi Beton	2.489,78	kg	0,2775												
	- Bekisting	100,43	m ²	0,1170												
	- Beton K-300	11,12	m ³	0,0996												
16	Balok B-16 (300x600)															
	- Besi Beton	733,30	kg	0,0817												
	- Bekisting	19,50	m ²	0,0227												
	- Beton K-300	2,16	m ³	0,0193												
17	Balok B-17 (300x600)															
	- Besi Beton	2.071,67	kg	0,2309												
	- Bekisting	46,80	m ²	0,0545												
	- Beton K-300	5,18	m ³	0,0464												
18	Balok B-18 (300x600)															
	- Besi Beton	1.136,11	kg	0,1266												
	- Bekisting	45,83	m ²	0,0534												
	- Beton K-300	5,08	m ³	0,0454												

TIME SCHEDULE
PROYEK GRAND SERITI HOTEL
PEKERJAAN STRUKTUR
JL. HEGARMAHA NO.9, BANDUNG

NO.	ITEM PEKERJAAN	VOLUME	SAT.	BOBOT	TAHUN 2007											KETERANGAN
					21-Jul P-1	28-Jul P-2	04-Agust P-3	11-Agust P-4	18-Agust P-5	25-Agust P-6	01-Sep P-7	08-Sep P-8	15-Sep P-9	22-Sep P-10	29-Sep P-11	
19	Balok B-19 (300x600)															
	- Besi Beton	161,15	kg	0,0180												
	- Bekisting	5,85	m ²	0,0068												
	- Beton K-300	0,65	m ³	0,0058												
20	Balok B-20 (300x600)															
	- Besi Beton	1.146,79	kg	0,1278												
	- Bekisting	39,00	m ²	0,0454												
	- Beton K-300	4,32	m ³	0,0387												
21	Balok B-21 (300x600)															
	- Besi Beton	682,07	kg	0,0760												
	- Bekisting	19,50	m ²	0,0227												
	- Beton K-300	2,16	m ³	0,0193												
22	Balok B-22 (300x600)															
	- Besi Beton	1.291,70	kg	0,1440												
	- Bekisting	20,80	m ²	0,0242												
	- Beton K-300	2,30	m ³	0,0206												
23	Balok B-23 (300x600)															
	- Besi Beton	465,55	kg	0,0519												
	- Bekisting	16,90	m ²	0,0197												
	- Beton K-300	1,87	m ³	0,0168												
24	Balok B-24 (300x600)															
	- Besi Beton	248,47	kg	0,0277												
	- Bekisting	8,45	m ²	0,0098												
	- Beton K-300	0,94	m ³	0,0084												
25	Balok B-25 (300x600)															
	- Besi Beton	247,85	kg	0,0276												
	- Bekisting	10,40	m ²	0,0121												
	- Beton K-300	1,15	m ³	0,0103												
26	Balok B-26 (300x600)															
	- Besi Beton	93,51	kg	0,0104												
	- Bekisting	3,64	m ²	0,0042												
	- Beton K-300	0,40	m ³	0,0036												
27	Balok B-27 (400x600)															
	- Besi Beton	150,97	kg	0,0168												
	- Bekisting	5,04	m ²	0,0059												
	- Beton K-300	0,69	m ³	0,0062												
28	Balok B-28 (400x600)															
	- Besi Beton	81,42	kg	0,0091												
	- Bekisting	2,52	m ²	0,0029												
	- Beton K-300	0,35	m ³	0,0031												
29	Plat (t=12cm)															
	- Wiremesh M7 (Double Layer)	816,75	m ²	1,0868												
	- Besi Beton	202,55	kg	0,0226												
	- Bekisting	816,75	m ²	0,9513												
	- Beton K-300	98,01	m ³	0,8774												
	- Water proofing	816,75	m ²	1,1590												
30	Kolom K-1 (400x800)															

TIME SCHEDULE
PROYEK GRAND SERITI HOTEL
PEKERJAAN STRUKTUR
JL. HEGARMANAH NO.9, BANDUNG

NO.	ITEM PEKERJAAN	VOLUME	SAT.	BOBOT	TAHUN 2007											KETERANGAN
					21-Jul P-1	28-Jul P-2	04-Agust P-3	11-Agust P-4	18-Agust P-5	25-Agust P-6	01-Sep P-7	08-Sep P-8	15-Sep P-9	22-Sep P-10	29-Sep P-11	
	- Besi Beton	2.812,16	kg	0,3134												
	- Bekisting	96,36	m ²	0,1232												
	- Beton K-300	12,85	m ³	0,1150												
31	Kolom K-2 (400x800)															
	- Besi Beton	1.278,25	kg	0,1425												
	- Bekisting	43,80	m ²	0,0560												
	- Beton K-300	5,84	m ³	0,0523												
32	Kolom K-3 (400x800)															
	- Besi Beton	225,41	kg	0,0251												
	- Bekisting	8,76	m ²	0,0112												
	- Beton K-300	1,17	m ³	0,0105												
33	Kolom K-4 (600x600)															
	- Besi Beton	721,59	kg	0,0804												
	- Bekisting	26,28	m ²	0,0336												
	- Beton K-300	3,94	m ³	0,0353												
34	Kolom K-5 (250x500)															
	- Besi Beton	418,14	kg	0,0466												
	- Bekisting	16,43	m ²	0,0210												
	- Beton K-300	1,37	m ³	0,0123												
35	Kolom K-6 (400x800)															
	- Besi Beton	225,41	kg	0,0251												
	- Bekisting	8,76	m ²	0,0112												
	- Beton K-300	1,17	m ³	0,0105												
36	Kolom K-7 (400x800)															
	- Besi Beton	555,22	kg	0,0619												
	- Bekisting	17,52	m ²	0,0224												
	- Beton K-300	2,34	m ³	0,0209												
37	Kolom K-8 (400x800)															
	- Besi Beton	590,02	kg	0,0658												
	- Bekisting	17,52	m ²	0,0224												
	- Beton K-300	2,34	m ³	0,0209												
38	Kolom K-9 (400x800)															
	- Besi Beton	1.143,56	kg	0,1275												
	- Bekisting	35,04	m ²	0,0448												
	- Beton K-300	4,67	m ³	0,0418												
39	Tangga Front Office ke LT. 4															
	- Besi Beton	117,48	kg	0,0131												
	- Bekisting	3,71	m ²	0,0043												
	- Beton K-300	0,50	m ³	0,0045												
40	Tangga Depan ke LT. 4															
	- Besi Beton	271,10	kg	0,0302												
	- Bekisting	8,55	m ²	0,0100												
	- Beton K-300	1,16	m ³	0,0103												
	Sub Total IV.D.															
D	LANTAI 4 (EMPAT)															
1	Balok B-1 (150x300)															
	- Besi Beton	123,55	kg	0,0138												

TIME SCHEDULE
PROYEK GRAND SERITI HOTEL
PEKERJAAN STRUKTUR
JL. HEGARMANAH NO.9, BANDUNG

NO.	ITEM PEKERJAAN	VOLUME	SAT.	BOBOT	TAHUN 2007											KETERANGAN
					21-Jul P-1	28-Jul P-2	04-Agust P-3	11-Agust P-4	18-Agust P-5	25-Agust P-6	01-Sep P-7	08-Sep P-8	15-Sep P-9	22-Sep P-10	29-Sep P-11	
	- Bekisting	3,80	m ²	0,0045												
	- Beton K-300	0,19	m ³	0,0017												
2	Balok B-2 (200x400)															
	- Besi Beton	421,91	kg	0,0472												
	- Bekisting	15,16	m ²	0,0178												
	- Beton K-300	1,06	m ³	0,0095												
3	Balok B-3 (200x400)															
	- Besi Beton	249,36	kg	0,0279												
	- Bekisting	8,96	m ²	0,0105												
	- Beton K-300	0,63	m ³	0,0056												
4	Balok B-4 (200x400)															
	- Besi Beton	1.723,91	kg	0,1929												
	- Bekisting	48,00	m ²	0,0563												
	- Beton K-300	3,36	m ³	0,0302												
5	Balok B-5 (200x400)															
	- Besi Beton	142,49	kg	0,0159												
	- Bekisting	5,12	m ²	0,0060												
	- Beton K-300	0,36	m ³	0,0032												
6	Balok B-6 (200x400)															
	- Besi Beton	44,69	kg	0,0050												
	- Bekisting	1,12	m ²	0,0013												
	- Beton K-300	0,08	m ³	0,0007												
7	Balok B-7 (200x400)															
	- Besi Beton	70,82	kg	0,0079												
	- Bekisting	1,92	m ²	0,0023												
	- Beton K-300	0,13	m ³	0,0012												
8	Balok B-8 (200x400)															
	- Besi Beton	296,15	kg	0,0331												
	- Bekisting	9,60	m ²	0,0113												
	- Beton K-300	0,67	m ³	0,0060												
9	Balok B-9 (200x400)															
	- Besi Beton	961,84	kg	0,1076												
	- Bekisting	28,40	m ²	0,0333												
	- Beton K-300	1,99	m ³	0,0179												
10	Balok B-10 (300x400)															
	- Besi Beton	570,16	kg	0,0638												
	- Bekisting	14,40	m ²	0,0169												
	- Beton K-300	1,34	m ³	0,0121												
11	Balok B-11 (300x600)															
	- Besi Beton	324,92	kg	0,0364												
	- Bekisting	11,05	m ²	0,0130												
	- Beton K-300	1,22	m ³	0,0110												
12	Balok B-12 (300x600)															
	- Besi Beton	1.427,45	kg	0,1597												
	- Bekisting	46,80	m ²	0,0549												
	- Beton K-300	5,18	m ³	0,0466												
13	Balok B-13 (300x600)															

TIME SCHEDULE
PROYEK GRAND SERITI HOTEL
PEKERJAAN STRUKTUR
JL. HEGARMANAH NO.9, BANDUNG

NO.	ITEM PEKERJAAN	VOLUME	SAT.	BOBOT	TAHUN 2007											KETERANGAN
					21-Jul P-1	28-Jul P-2	04-Agust P-3	11-Agust P-4	18-Agust P-5	25-Agust P-6	01-Sep P-7	08-Sep P-8	15-Sep P-9	22-Sep P-10	29-Sep P-11	
	- Besi Beton	699,02	kg	0,0782												
	- Bekisting	19,31	m ²	0,0227												
	- Beton K-300	2,14	m ³	0,0192												
14	Balok B-14 (300x600)															
	- Besi Beton	1.956,88	kg	0,2190												
	- Bekisting	69,55	m ²	0,0816												
	- Beton K-300	7,70	m ³	0,0692												
15	Balok B-15 (300x600)															
	- Besi Beton	2.825,59	kg	0,3162												
	- Bekisting	100,43	m ²	0,1179												
	- Beton K-300	11,12	m ³	0,0999												
16	Balok B-16 (300x600)															
	- Besi Beton	855,59	kg	0,0957												
	- Bekisting	19,50	m ²	0,0229												
	- Beton K-300	2,16	m ³	0,0194												
17	Balok B-17 (300x600)															
	- Besi Beton	2.071,67	kg	0,2318												
	- Bekisting	46,80	m ²	0,0549												
	- Beton K-300	5,18	m ³	0,0465												
18	Balok B-18 (300x600)															
	- Besi Beton	1.442,58	kg	0,1614												
	- Bekisting	45,83	m ²	0,0538												
	- Beton K-300	5,08	m ³	0,0456												
19	Balok B-19 (300x600)															
	- Besi Beton	182,89	kg	0,0205												
	- Bekisting	5,85	m ²	0,0069												
	- Beton K-300	0,65	m ³	0,0058												
20	Balok B-20 (300x600)															
	- Besi Beton	1.146,79	kg	0,1283												
	- Bekisting	39,00	m ²	0,0458												
	- Beton K-300	4,32	m ³	0,0388												
21	Balok B-21 (300x600)															
	- Besi Beton	682,07	kg	0,0763												
	- Bekisting	19,50	m ²	0,0229												
	- Beton K-300	2,16	m ³	0,0194												
22	Balok B-22 (300x600)															
	- Besi Beton	1.291,70	kg	0,1445												
	- Bekisting	20,80	m ²	0,0244												
	- Beton K-300	2,30	m ³	0,0207												
23	Balok B-23 (300x600)															
	- Besi Beton	591,13	kg	0,0661												
	- Bekisting	16,90	m ²	0,0198												
	- Beton K-300	1,87	m ³	0,0168												
24	Balok B-24 (300x600)															
	- Besi Beton	427,59	kg	0,0478												
	- Bekisting	12,61	m ²	0,0148												
	- Beton K-300	1,40	m ³	0,0125												

TIME SCHEDULE
PROYEK GRAND SERITI HOTEL
PEKERJAAN STRUKTUR
JL. HEGARMANAH NO.9, BANDUNG

NO.	ITEM PEKERJAAN	VOLUME	SAT.	BOBOT	TAHUN 2007											KETERANGAN
					21-Jul P-1	28-Jul P-2	04-Agust P-3	11-Agust P-4	18-Agust P-5	25-Agust P-6	01-Sep P-7	08-Sep P-8	15-Sep P-9	22-Sep P-10	29-Sep P-11	
25	Balok B-25 (300x600)															
	- Besi Beton	286,49	kg	0,0321												
	- Bekisting	10,40	m ²	0,0122												
	- Beton K-300	1,15	m ³	0,0103												
26	Balok B-26 (300x600)															
	- Besi Beton	146,83	kg	0,0164												
	- Bekisting	5,33	m ²	0,0063												
	- Beton K-300	0,59	m ³	0,0053												
27	Balok B-27 (400x600)															
	- Besi Beton	150,97	kg	0,0169												
	- Bekisting	5,04	m ²	0,0059												
	- Beton K-300	0,69	m ³	0,0062												
28	Balok B-28 (400x600)															
	- Besi Beton	142,28	kg	0,0159												
	- Bekisting	2,52	m ²	0,0030												
	- Beton K-300	0,35	m ³	0,0031												
29	Plat (t=12cm)															
	- Wiremesh M7 (Double Layer)	816,75	m ²	1,0895												
	- Besi Beton	202,55	kg	0,0227												
	- Bekisting	816,75	m ²	0,9586												
	- Beton K-300	98,01	m ³	0,8803												
	- Water proofing	816,75	m ²	1,1590												
31	Kolom K-1 (400x800)															
	- Besi Beton	3.144,80	kg	0,3519												
	- Bekisting	96,36	m ²	0,1242												
	- Beton K-300	12,85	m ³	0,1154												
32	Kolom K-2 (400x800)															
	- Besi Beton	1.429,45	kg	0,1600												
	- Bekisting	43,80	m ²	0,0565												
	- Beton K-300	5,84	m ³	0,0525												
33	Kolom K-3 (400x800)															
	- Besi Beton	285,89	kg	0,0320												
	- Bekisting	8,76	m ²	0,0113												
	- Beton K-300	1,17	m ³	0,0105												
34	Kolom K-4 (600x600)															
	- Besi Beton	857,67	kg	0,0960												
	- Bekisting	26,28	m ²	0,0339												
	- Beton K-300	3,94	m ³	0,0354												
35	Kolom K-5 (250x500)															
	- Besi Beton	365,94	kg	0,0409												
	- Bekisting	16,43	m ²	0,0212												
	- Beton K-300	1,37	m ³	0,0123												
36	Kolom K-6 (400x800)															
	- Besi Beton	285,89	kg	0,0320												
	- Bekisting	8,76	m ²	0,0113												
	- Beton K-300	1,17	m ³	0,0105												
37	Kolom K-7 (400x800)															

TIME SCHEDULE
PROYEK GRAND SERITI HOTEL
PEKERJAAN STRUKTUR
JL. HEGARMANAH NO.9, BANDUNG

NO.	ITEM PEKERJAAN	VOLUME	SAT.	BOBOT	TAHUN 2007											KETERANGAN
					21-Jul P-1	28-Jul P-2	04-Agust P-3	11-Agust P-4	18-Agust P-5	25-Agust P-6	01-Sep P-7	08-Sep P-8	15-Sep P-9	22-Sep P-10	29-Sep P-11	
	- Besi Beton	676,18	kg	0,0757												
	- Bekisting	17,52	m ²	0,0226												
	- Beton K-300	2,34	m ³	0,0210												
38	Kolom K-8 (400x800)															
	- Besi Beton	710,98	kg	0,0796												
	- Bekisting	17,52	m ²	0,0226												
	- Beton K-300	2,34	m ³	0,0210												
39	Kolom K-9 (400x800)															
	- Besi Beton	1.143,56	kg	0,1280												
	- Bekisting	35,04	m ²	0,0452												
	- Beton K-300	4,67	m ³	0,0420												
40	Tangga Front Office ke LT. Mezanine															
	- Besi Beton	117,48	kg	0,0131												
	- Bekisting	3,71	m ²	0,0048												
	- Beton K-300	0,50	m ³	0,0045												
41	Tangga Depan ke LT. Mezanine															
	- Besi Beton	271,10	kg	0,0303												
	- Bekisting	8,55	m ²	0,0110												
	- Beton K-300	1,16	m ³	0,0104												
	Sub Total IV.E.															
E	LANTAI 4A															
1	Balok B-1 (150x300)															
	- Besi Beton	105,34	kg	0,0118												
	- Bekisting	3,74	m ²	0,0044												
	- Beton K-300	0,18	m ³	0,0017												
2	Balok B-2 (200x400)															
	- Besi Beton	472,00	kg	0,0531												
	- Bekisting	16,96	m ²	0,0201												
	- Beton K-300	1,19	m ³	0,0107												
3	Balok B-3 (200x400)															
	- Besi Beton	150,37	kg	0,0169												
	- Bekisting	4,60	m ²	0,0054												
	- Beton K-300	0,32	m ³	0,0029												
4	Balok B-4 (200x400)															
	- Besi Beton	109,09	kg	0,0123												
	- Bekisting	3,92	m ²	0,0046												
	- Beton K-300	0,27	m ³	0,0025												
5	Balok B-5 (200x400)															
	- Besi Beton	71,25	kg	0,0080												
	- Bekisting	2,56	m ²	0,0030												
	- Beton K-300	0,18	m ³	0,0016												
6	Balok B-6 (200x400)															
	- Besi Beton	1.545,26	kg	0,1738												
	- Bekisting	36,00	m ²	0,0426												
	- Beton K-300	2,52	m ³	0,0227												
7	Balok B-7 (200x400)															
	- Besi Beton	758,64	kg	0,0853												

TIME SCHEDULE
PROYEK GRAND SERITI HOTEL
PEKERJAAN STRUKTUR
JL. HEGARMAH NO.9, BANDUNG

NO.	ITEM PEKERJAAN	VOLUME	SAT.	BOBOT	TAHUN 2007										KETERANGAN	
					21-Jul P-1	28-Jul P-2	04-Agust P-3	11-Agust P-4	18-Agust P-5	25-Agust P-6	01-Sep P-7	08-Sep P-8	15-Sep P-9	22-Sep P-10		29-Sep P-11
	- Bekisting	22,40	m ²	0,0265												
	- Beton K-300	1,57	m ³	0,0141												
8	Balok B-8 (200x400)															
	- Besi Beton	1.098,85	kg	0,1236												
	- Bekisting	25,60	m ²	0,0303												
	- Beton K-300	1,79	m ³	0,0161												
9	Balok B-9 (200x400)															
	- Besi Beton	159,62	kg	0,0180												
	- Bekisting	4,00	m ²	0,0047												
	- Beton K-300	0,28	m ³	0,0025												
10	Balok B-10 (200x400)															
	- Besi Beton	74,04	kg	0,0083												
	- Bekisting	2,40	m ²	0,0028												
	- Beton K-300	0,17	m ³	0,0015												
11	Balok B-11 (200x400)															
	- Besi Beton	54,55	kg	0,0061												
	- Bekisting	1,96	m ²	0,0023												
	- Beton K-300	0,14	m ³	0,0012												
12	Balok B-12 (300x400)															
	- Besi Beton	1.369,80	kg	0,1541												
	- Bekisting	32,40	m ²	0,0384												
	- Beton K-300	3,02	m ³	0,0272												
13	Balok B-13 (300x500)															
	- Besi Beton	722,26	kg	0,0812												
	- Bekisting	24,75	m ²	0,0293												
	- Beton K-300	2,57	m ³	0,0231												
14	Balok B-14 (400x600)															
	- Besi Beton	1.059,16	kg	0,1191												
	- Bekisting	25,20	m ²	0,0298												
	- Beton K-300	3,46	m ³	0,0311												
15	Balok B-15 (400x600)															
	- Besi Beton	377,43	kg	0,0425												
	- Bekisting	12,60	m ²	0,0149												
	- Beton K-300	1,73	m ³	0,0156												
16	Balok B-16 (400x600)															
	- Besi Beton	479,21	kg	0,0539												
	- Bekisting	12,60	m ²	0,0149												
	- Beton K-300	1,73	m ³	0,0156												
17	Balok B-17 (400x700)															
	- Besi Beton	1.123,81	kg	0,1264												
	- Bekisting	28,80	m ²	0,0341												
	- Beton K-300	4,18	m ³	0,0376												
18	Balok B-18 (300x600)															
	- Besi Beton	447,64	kg	0,0504												
	- Bekisting	16,25	m ²	0,0192												
	- Beton K-300	1,80	m ³	0,0162												
19	Balok B-19 (300x600)															

TIME SCHEDULE
PROYEK GRAND SERITI HOTEL
PEKERJAAN STRUKTUR
JL. HEGARMAH NO.9, BANDUNG

NO.	ITEM PEKERJAAN	VOLUME	SAT.	BOBOT	TAHUN 2007											KETERANGAN
					21-Jul P-1	28-Jul P-2	04-Agust P-3	11-Agust P-4	18-Agust P-5	25-Agust P-6	01-Sep P-7	08-Sep P-8	15-Sep P-9	22-Sep P-10	29-Sep P-11	
	- Besi Beton	114,60	kg	0,0129												
	- Bekisting	4,16	m ²	0,0049												
	- Beton K-300	0,46	m ³	0,0042												
20	Balok B-20 (300x600)															
	- Besi Beton	2.835,75	kg	0,3190												
	- Bekisting	86,31	m ²	0,1022												
	- Beton K-300	9,86	m ³	0,0889												
21	Balok B-21 (300x600)															
	- Besi Beton	537,17	kg	0,0604												
	- Bekisting	19,50	m ²	0,0231												
	- Beton K-300	2,16	m ³	0,0195												
22	Balok B-22 (300x600)															
	- Besi Beton	1.357,03	kg	0,1527												
	- Bekisting	46,15	m ²	0,0546												
	- Beton K-300	5,11	m ³	0,0461												
23	Balok B-23 (300x600)															
	- Besi Beton	312,31	kg	0,0351												
	- Bekisting	9,75	m ²	0,0115												
	- Beton K-300	1,08	m ³	0,0097												
24	Balok B-24 (300x600)															
	- Besi Beton	270,67	kg	0,0304												
	- Bekisting	8,45	m ²	0,0100												
	- Beton K-300	0,94	m ³	0,0084												
25	Balok B-25 (300x600)															
	- Besi Beton	1.581,56	kg	0,1779												
	- Bekisting	54,86	m ²	0,0650												
	- Beton K-300	6,08	m ³	0,0547												
26	Balok B-26 (300x600)															
	- Besi Beton	313,82	kg	0,0353												
	- Bekisting	7,80	m ²	0,0092												
	- Beton K-300	0,86	m ³	0,0078												
27	Balok B-27 (300x600)															
	- Besi Beton	167,30	kg	0,0188												
	- Bekisting	4,68	m ²	0,0055												
	- Beton K-300	0,52	m ³	0,0047												
28	Balok B-28 (300x600)															
	- Besi Beton	159,64	kg	0,0180												
	- Bekisting	4,16	m ²	0,0049												
	- Beton K-300	0,46	m ³	0,0042												
29	Balok B-29 (300x600)															
	- Besi Beton	444,57	kg	0,0500												
	- Bekisting	11,05	m ²	0,0131												
	- Beton K-300	1,22	m ³	0,0110												
30	Balok B-30 (300x600)															
	- Besi Beton	474,73	kg	0,0534												
	- Bekisting	13,00	m ²	0,0154												
	- Beton K-300	1,44	m ³	0,0130												

TIME SCHEDULE
PROYEK GRAND SERITI HOTEL
PEKERJAAN STRUKTUR
JL. HEGARMANAH NO.9, BANDUNG

NO.	ITEM PEKERJAAN	VOLUME	SAT.	BOBOT	TAHUN 2007											KETERANGAN
					21-Jul P-1	28-Jul P-2	04-Agust P-3	11-Agust P-4	18-Agust P-5	25-Agust P-6	01-Sep P-7	08-Sep P-8	15-Sep P-9	22-Sep P-10	29-Sep P-11	
31	Balok B-31 (300x600)															
	- Besi Beton	151,68	kg	0,0171												
	- Bekisting	3,77	m ²	0,0045												
	- Beton K-300	0,42	m ³	0,0038												
32	Balok B-32 (300x600)															
	- Besi Beton	1.341,58	kg	0,1509												
	- Bekisting	40,82	m ²	0,0483												
	- Beton K-300	4,52	m ³	0,0407												
33	Balok B-33 (300x600)															
	- Besi Beton	784,54	kg	0,0883												
	- Bekisting	19,50	m ²	0,0231												
	- Beton K-300	2,16	m ³	0,0195												
34	Balok B-34 (300x600)															
	- Besi Beton	733,30	kg	0,0825												
	- Bekisting	19,50	m ²	0,0231												
	- Beton K-300	2,16	m ³	0,0195												
35	Balok B-35 (300x600)															
	- Besi Beton	140,98	kg	0,0159												
	- Bekisting	4,16	m ²	0,0049												
	- Beton K-300	0,46	m ³	0,0042												
36	Plat (t=13cm)															
	- Wiremesh M7 (Double Layer)	816,75	m ²	1,0921												
	- Besi Beton	202,55	kg	0,0227												
	- Bekisting	816,75	m ²	0,9670												
	- Beton K-300	106,18	m ³	0,9566												
	- Water proofing	816,75	m ²	1,1590												
37	Kolom K-1 (250x250)															
	- Besi Beton	601,62	kg	0,0677												
	- Bekisting	22,50	m ²	0,0292												
	- Beton K-300	1,41	m ³	0,0127												
38	Kolom K-3 (300x300)															
	- Besi Beton	148,93	kg	0,0168												
	- Bekisting	4,50	m ²	0,0058												
	- Beton K-300	0,34	m ³	0,0030												
39	Kolom K-4 (250x250)															
	- Besi Beton	100,27	kg	0,0113												
	- Bekisting	3,75	m ²	0,0049												
	- Beton K-300	0,23	m ³	0,0021												
40	Kolom K-5 (250x250)															
	- Besi Beton	181,11	kg	0,0204												
	- Bekisting	11,25	m ²	0,0146												
	- Beton K-300	0,70	m ³	0,0063												
41	Tangga ke LT. Atas															
	- Besi Beton	117,48	kg	0,0132												
	- Bekisting	3,71	m ²	0,0048												
	- Beton K-300	0,50	m ³	0,0045												